F18 818

KOLAR DIVISION.

NOTICE.

The attention of the public is invited to the notification published in the *Mysore Gazette*, Part IV, page 746, calling for tenders for restoring Ghatti Madamangala Tank, Registered No. 602 of Bowringpet Taluk.

NOTICE.

The attention of the public is invited to the notification published in the *Mysore Gazette*, Part IV of page 766 calling for tenders for restoring Katenhalli tank, Register No. 46 of Gudibanda Sub-Taluk.

NOTICE.

The attention of the public is invited to the notification published in the *Mysore Gazette*, Part IV, page 766, calling for tenders for restoring Balasandra Settikere, Register No. 146 of Gudibanda Sub-Taluk.

V. V. KARVE,
Offg Executive Engineer.

TUMKUR DIVISION.

Dated 20th August 1918.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Tumkur Division, up to 16th September 1918, for constructing Sub-Registrar's Office and Bonded Warehouse at Tiptur. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1919.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Tumkur, between the hours of 11 A.M. and 5 P.M., except Sundays and holidays.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 300 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing Sub-Registrar's Office and Bonded Warehouse at Tiptur," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, Northern Circle, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

ABSTRACT.

Item No.	Items of work	Per	Quantity
1	Earthwork excavation and filling basement	C. yd.	54
2	Burnt stone in chunam	C. ft.	1,903
3	Burnt brick in chunam	"	3,169
4	Burnt stone slabs one line dressed	S. ft.	640
5	Plastering with chunam	Sq.	60·55
6	Chunam pointing	"	2·31
7	White and colourwashing	"	62·80
8	Teakwood work with wood oiling	C. ft.	168·00
9	Roofing with 1st class Mangalore tiles on teak rafters, etc.	Sq.	17·34
10	Ridge tiles set in mortar and cement pointing	R. ft.	52
11	Chunam borders	"	145
12	Terraced roofing	Sq.	5·81
13	Cornice 9" thick	R. ft.	258
14	Cutting channels in the carbel and stone pillars for brassummer to rest ...	Each	28
15	Teak ornamental eive board	R. ft.	113
16	Parapet wall over the terrace	"	113
17	Teakwood panelled door with iron clamps, etc., complete	S. ft.	114
18	Teakwood battened doors with four folded shutters and iron clamps, etc., complete and the side frame be fixed in silt slab after cutting slabs 3" in depth to receive the side frame	"	41
19	Teakwood windows inside glazed and outside panelled shutters with ½" iron bars, iron clamps, etc., complete.	"	158
20	Teakwood ventilators with expanded metal shutters and iron clamps, etc., complete.	"	21
21	Teak pendents	Each	2
22	Teakwood finials	"	2
23	Silicate chocolate painting	Sq.	11·50
24	Flooring with Cuddapah slabs over 3" concrete and cement pointing.	"	12·06
25	Flooring with granite slabs 3" to 4" over sand flooring of 6" to tap and spirit room.	"	264
26	Expanded metal partition with four-folded shutters with teak frames and painting, etc., complete.	S. ft.	183
27	Teakwood screen with double shutters including iron works and painting, etc, complete.	"	84
27 (a)	Teakwood windows inside glazed and outside expanded metal fixed iron bars, etc., complete.	"	95
28	Clearing site, levelling ground and tarring the portion of woodwork in wall and forming ramp in the side of verandah of spirit room.	Lump sum	Rs.

Dated 20th August 1918.

1. Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Tumkur Division, up to 16th September 1918, for constructing Sub-Registrar's Office and Bonded Warehouse at Chiknayakanhalli. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1919.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Tumkur, between the hours of 11 A.M. and 5 P.M., except Sundays and holidays.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 300, in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing Sub-Registrar's Office and Bonded Warehouse at Chiknayakanhalli," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, Northern Circle, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

ABSTRACT.

No.	Items of work	Per	Quantity
1	Earthwork excavation and filling in basement	C. yd.	54
2	Burnt stone in clay	C. ft.	1,912
2a	Burnt brick in clay	"	2,555
3	Burnt brick in mortar	"	584
4	Burnt stone slabs, one line, dressed	S. ft.	590
5	Plastering with chunam	Sq.	69·55
6	Chunam pointing	"	3·45
7	White and colour washing	"	60·55
8	Teakwood work with wood oiling	C. ft.	165·4
9	Roofing with 1st class Mangalore tiles on teak reepers	Sq.	17·60
10	Ridge tiles set in mortar	R. ft.	52
11	Chunam borders	"	144
12	Pucca terrace	"	6·07
13	Cornice, 9" thick	"	257
14	Cutting channels in the carbel and stone pillars for bressummers to rest	Each,	38
15	Teak ornamental eave boards	R. ft.	113
16	Parapet wall over terrace	"	113
17	Teakwood panelled doors with iron clamps, etc., complete	S. ft.	114
18	Teakwood battened doors, with four folded, shutters and iron clamps, etc, complete and side frames be fixed in sill slab after cutting the slab. 3" in depth to receive the side frame.	"	44
19	Teakwood windows, inside glazed and outside panelled shutters with iron bars, iron clamps, etc., complete.	"	157
19a	Teakwood windows, inside glazed and outside expanded metal shutters and fixed iron bars, etc., complete.	"	95
20	Teakwood ventilators with expanded metal shutters, iron clamps, etc., complete.	"	21
21	Teakwood finials	Each	2
22	Teakwood pendants	"	4
23	Silicate chocolate painting	Sq.	12·85
23a	Providing clerestories in top and spirit room	Lump	sum.
24	Flooring with Cuddapah slabs, over 3" concrete and cement pointing	Sq.	12·06
25	Flooring with granite slab, 3" to 4" thick, over sandbed and cement pointing.	"	2·64
26	Expanded metal partition with four folded shutters with teak frames and paintings, etc., complete.	S. ft.	135
27	Teakwood screen with double shutters including iron work and painting, etc., complete.	"	84
28	Clearing site, levelling ground and forming ramp in the side of verandah of spirit room.	Lump	sum.
29	Tarring wood work	"	"
30	Rain water down pipe zinc, 4" dia.	R. ft.	112·5

Abstract Notification.

Attention of the public is invited to page 747 of Part IV of *Mysore Gazette*, dated 15th August 1918, calling for tenders for constructing cows' shed and calfs' shed at Kunigal. The last date for tender is 26th August 1918, and the earnest money is Rs. 300.

Abstract Notification.

Attention of the public is invited to pages 747—748 of Part IV of *Mysore Gazette*, dated 15th August 1918, calling for tenders for constructing Sub-Registrar's Office and Bonded Warehouse at Maddagiri. The last date for tender is 26th August 1918. Earnest money to accompany tender is Rs. 150.

Abstract Notification.

Attention of the public is invited to page 767 of Part IV of *Mysore Gazette*, dated 22nd August 1918, calling for tenders for restoring Jindigere Tank, Regd. No. 376, Gubbi Taluk. The last date of tender is 2nd September 1918 and the earnest money is Rs. 200.

N. G. KRISHNA IYENGAR,
Offg. Executive Engineer.

NEW PALACE DIVISION.

The attention of the public is invited to the notification published on page 768, Part IV of *Mysore Gazette*, dated 22nd August 1918, calling for sealed tenders for the supply of Rolled Steel Girders, the date of receiving the tenders being 12th September 1918, instead of 2nd (Monday) September 1918, as noted therein.

S. H. LAKSHMINARASAPPA,
Architectural Executive Engineer in charge of New Palace Division, Mysore.

HASSAN DIVISION.

Dated 17th August 1918.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Hassan Division, up to 10th September 1918, for constructing an Annachattram at Hassan. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1919.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Hassan between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees 250 in cash or Government Promissory Notes, as earnest money and be superscribed "Tender for constructing an Annachatram at Hassan," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office, in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract estimate of constructing Annachattram at Hassan.

Details of work	Per	Rate	Quantity	Cost
		Rs. a. p.		Rs.
Earthwork excavation and filling in basement	C. yd.		132	
Stone in clay for foundation and basement	C. ft.		5,578	
Burnt brick in clay superstructure	"		6,785	
Burnt brick in chunam superstructure	"		785	
Burnt stone slabs, 4" thick	S. ft.		681	
Burnt stone pillars dressed (9'×8"×8")	Each		12	
Do (15'×8'×8')	"		6	
Honnewood battened doors including iron works, etc., complete	S. ft.		278	
Do do windows including iron works and bars, etc.	"		243	
Do work wrought and put up	C. ft.		437	
Do trusses including fixing, etc.	Each		4	
Roofing with 1st class Mangalore tiles on teak reepers	Sq.		48·77	
Ridge tiles set in mortar	R. ft.		306	
Chunam plastering	Sq.		29·60	
Mud plastering	"		109·58	
White and colour-washing	"		139·18	
Painting to doors and windows	"		10·42	
Zinc sheets for valleys	S. ft.		258	
Wood oiling to rafters	L. S. Rs.		...	
Clearing site and levelling ground	"		...	
Constructing sinks and drains	"		...	
Repairing the existing well	"		...	
Flooring with 9" gravel including lead	C. yd.		86	

R. W. SCALDWELL,